

TO CONTRACT DOCUMENTS ENTITLED:

PROJECT MANUAL FOR: **Various Locations – Hatch and Schurz Hall Tuck Pointing**

PROJECT NUMBER: **CP252341**

ADVERTISEMENT DATE: 2025-12-15

PREPARED FOR: The Curators of the University of Missouri

PREPARED BY: PWArchitects, Inc.
ATTN: Eric Roselle, AIA
2120 Forum Blvd, Ste 101
Columbia, MO 65203
Phone: (573) 449-2683
Fax: (573) 442-6213

2026-01-23



Drawings and Specifications for the above noted project and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect:

GENERAL:

- QUESTION: *"Since there are no existing roof tieback anchors, can the roof be penetrated to install tieback anchors in the concrete deck that may be required for swing stage access? If so, would the University provide a roofer to patch the roof after the tieback anchors have been removed (for warranty purposes)?"*

ANSWER:

Roof tieback anchors can be installed but will need to be removed at the end of the project. If anchors are installed:

- The contractor is responsible for verifying field conditions.
- Prior to installing any such anchors a roof plan showing the anchors and detailing how they are to be installed must be submitted for Owner and Architect review. Only on approval can the anchors be installed.
- The plan must clearly illustrate and note how a waterproof envelope will be maintained at the penetrations, while anchors and staging are set.
- The anchors must be installed, removed, and any damage repaired by a licensed roofing contractor at no additional cost to the Owner. All damage must be repaired to the satisfaction of the Owner's Representative.

END OF ADDENDUM #2